

## Repairing and improving the Mandy Market at Mysore.

Serial No.	Description of work	Unit of work	Provision stalls	Vegetable stalls	Mutton, fish and offal stalls
1	Earthwork excavation and filling in basement	Cubic yard	62		
2	Chunam mortar concrete	feet	276		
3	Burnt brick in mud	Do	800		
4	Burnt brick in mortar	Do	2,956		
5	Plastering with chunam	Square	48.50		
6	Burnt stone slabs 6" thick including two lines dressing, fixing and pointing with cement, etc., complete.	Square feet	218		
7	Burnt stone bed slabs 4" to 6" thick	Do	50		
8	Burnt stone pillars 4" thick including chamfering edges, two lines dressing and cutting of grooves to receive bressommiers, etc., complete.	Do		1,200	
9	Burnt stone slabs 4" to 6" thick including 1 lime dressing, fixing, pointing, etc., complete.	Do		1,242	
10	Removing old Arcot tiles, reapers and flat tiles, etc., including carting debris and stocking materials.	Do	128.50		
11	Removing the existing deteriorated Bengal terrace and carting debris, etc.	Do			40.60
12	Teakwood work wrought and put up	Cubic feet	224.66	510	
13	Roofing with 1st class Mangalore tiles on teak reapers, etc., complete.	Square feet	131.08	63.04	
14	Roofing with Bengal terrace using the available flat tiles got from dismantling the old roof and removing teak reapers wherever necessary.	Do			40.60
15	Roofing with pukka terrace with flat tiles	Do	16.50		
16	Ridge tiles set in mortar including cement pointing	Rft.	478		
17	Removing and refixing old eave boards with repairs wherever necessary.	Do	813		
18	Teakwood ornamental eave board new 9" wide and 1" thick including fixing	Do	160		
19	Teakwood ordinary eave board new 9" wide and 1" thick including fixing.	Do		972	337
20	Flooring with Cuddappa slabs on 3" concrete bed including cement pointing, complete.	Square feet	61.7	30.78	21.78
21	Cornice 9" thick	Rft.	68		
22	Do 6" thick	Do	298		
23	Ornamental parapet wall 2 to 2½ high, etc., complete.	Do	128		
24	Plain parapet wall 3' high, etc., complete	Do	60		
25	Do 2' high	Do			518
26	Do 1½'	Do			341
27	Stone bases for pillars	Each	16		
28	Masonry finials, complete	Do	6		
29	Ornamental pediments, complete	Do			
30	Teak wood windows with iron bars, glazed shutters inside and pannelled outside, etc., complete.	Square feet	48		
31	Teak wood doors with battened shutters including bolts, hinges, etc., complete.	Do	1,200		
32	Teak wood rectangular ventilators glazed with ropes, etc., complete.	Do	16		
33	Chocolate painting or any other silicate painting (two coats).	Do	27.00		
34	Wood oiling two coats	Do	22.00	10.00	20.00
35	Whitewashing two coats	Do	35.00		
36	Colourwashing two coats	Do	13.50		
37	Sundry repairs to flooring, existing walls, etc., wherever necessary.	Lumpsum			8.8.
38	Constructing cement concrete semi peg top sectional drain of 3" radius.	Rft.			534
39	Carting of earth including spreading, flooring and consolidation.	Cubic yard			